



CLOPAY MODELS H000, H001, H100


REVISIONS					
REV. NO.	ZONE:	DATE:	ECN NO.	APPVD:	DESCRIPTION
00	-	4/24/03	ER1022	SH	ORIGINAL ISSUE
01	-	12/23/03	-	RK	STRUT PATTERN WAS 'ONE EA. SECTION EXCEPT #3'







VERTICAL JAMB ATTACHMENT (WOOD FRAME BUILDINGS):
OPTION 1: 3/8" x 3" (1-1/2" EMBED) LAG SCREWS ON 24" CENTERS. 1-1/8" O.D. MIN. WASHER REQUIRED. LAG SCREWS MAY BE COUNTERSUNK (NOT REQUIRED) TO PROVIDE FLUSH MOUNTING SURFACE.
OPTION 2: 16D x 3-1/2" (2" EMBED) COMMON WIRE NAILS ON 13" CENTERS. (HORIZONTAL JAMBS DO NOT TRANSFER LOAD.)

THIS DOOR MEETS OR EXCEEDS THE DESIGN LOADS FOR THE WIND SPEEDS LISTED BELOW ACCORDING TO THE 2000 INTERNATIONAL BUILDING/RESID. CODE FOR THE FOLLOWING CONDITIONS: 1) ENCLOSED BUILDING, 2) DOOR HAS 2' OF WIDTH IN BUILDING'S END ZONE, 3) IMPORTANCE FACTOR OF 1.0, 4) ANY ROOF SLOPE, AND 5) 50% SAFETY FACTOR.

WIND SPEED (MPH)	≤ 90
EXPOSURE LEVEL	B
MEAN ROOF HEIGHT	30'




NOTE:
 ALL HINGES, TOP BRACKETS, AND BOTTOM BRACKETS ARE ATTACHED WITH #14x5/8" SHEET METAL SCREWS.




DESIGN ENGINEER: MARK WESTERFIELD, P.E.
 FLORIDA P.E. #48495, NC P.E. #23832, TEXAS P.E. #91513

DESIGN LOADS: +13.0 P.S.F. & -15.0 P.S.F.
 TEST LOADS: +19.5 P.S.F. & -22.5 P.S.F.



NOTE: DOUBLE TRACK LOW HEADROOM AVAILABLE. 3" TRACK AVAILABLE AS NEEDED.

DOOR HEIGHT	"L"
8'-6"	94"
9'-0"	100"
9'-6"	106"
10'-0"	112"
10'-6"	118"
11'-0"	124"
11'-6"	130"
12'-0"	136"



NOTE: THE DESIGN OF THE SUPPORTING STRUCTURAL ELEMENTS SHALL BE THE RESPONSIBILITY OF THE PROFESSIONAL OF RECORD FOR THE BUILDING OR STRUCTURE AND IN ACCORDANCE WITH CURRENT BUILDING CODES FOR THE LOADS LISTED ON THIS DRAWING.

NOTICE:
 Confidential/Proprietary information of CLOPAY BUILDING PRODUCTS CO. is contained herein and may not be disclosed, used, duplicated, made available, or distributed without its prior consent. Failure to observe this notice may result in liability for any damages and losses resulting therefrom.

Unless Stated Otherwise
TOLERANCES are

.0	= ± .03
.00	= ± .015
.000	= ± .005
.0000	= ± .001
Degrees	= ± 1/2°

Third Angle Projection

Unless Stated Otherwise
 DIMENSIONS ARE IN INCHES.

Glopay Building Products Company
 8585 Duke Boulevard
 Mason, OH 45040
 Tel. No. 1-513-381-4800
 Fax No. 1-513-762-3519

DESIGNER: MARK WESTERFIELD, P.E.
 FLORIDA P.E. #48495, NC P.E. #23832, TEXAS P.E. #91513

DESCRIPTION: H000/H001/H100 SC +13.0/-15.0 PSF DES.

DRAWN BY: DAS	DATE: 11/27/02	SCALE: NTS	DWG. B
CHECKED BY:	DATE:	SHEET 1 OF 1	SIZE
DWG. NO.: 102710	REV. NO. 01		